GOVERNMENT OF MYSORE ELECTRICAL DEPARTMENT.

Notification dated 1st October 1931.

Notice is hereby given that sealed tenders will be received at the Office of the Chief Electrical Engineer, Bangalore up to 2 P.M., on 30th October 1931, for constructing Electrical Buildings at Seringapatam.

1. The tenders will be opened in public at 2 P.M., on 30th October 1931. The work should be completed within four months and the monthly progress should not be less than Rs. 1,400.

2. The plans, detailed estimates and the conditions may be seen at the Chief Electrical Engineer's Office, Bangalore, on all working days during the office working hours.

3. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates should be in figures as well as in words.

4. Each tender must be accompanied by a deposit of Rs. 300 in cash or in Government Promissory Notes, as earnest money and be superscribed "Tenders for constructing Electrical Buildings at Seringapatam" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Electrical Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender. The Chief Electrical Engineer also reserves the right to accept or reject any portion of the tender.

6. Within eight days of the award of the tender the successful tenderer will be required to execute the usual contract bond, in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful tenderer will be posted on the notice board in the Chief Electrical Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The construction work should be started within a week from the date of Notification of the acceptance.

10. Water for construction should be got at the contractor's own expense.

11. Specifications for works are those recognised by the Mysore Public Works Department and Marryot's specifications.

12. The contractor should be bound by the conditions of the schedule of contract of the Electrical Department.

Constructing Office and Stores.

Sl. No.	Items	Unit	Quantity	Rate
1	Earthwork excavation for foundation including filling in basement.	C.yd.	34	
2a	Concrete stone jelly in lime mortar foundation ...	C.ft.	319	
b	Stone in lime mortar foundation and basement including through stones at 6'—0" centre to centre in every course.	„	769	
c	Burnt brick in clay superstructure	„	1,233	
d	Burnt brick in lime mortar superstructure ...	„	111	
e	Burnt stone slabs 6" thick roughly dressed and fixed in mortar.	S.ft.	95	
f	Stone slabs 3" thick exposed parts one line dressed and set in mortar.	„	7	
g	Brick in mortar pillars 1·1/8' square and 9'—9" high including base and capital and cement plastering ½" thick, etc., complete as per design.	Each	4	
h	Chunam plastering two coats	Sqr.	26·03	
i	Chunam pointing with thread lines	„	1·69	
j	White and colour washing two coats	„	27·72	
k	Plain brick cornice 6" projection as per design ...	R.ft.	134	
l	Brick in mortar parapet wall 9" thick as per design ...	„	134	
m	Chunam moulding in front of wall between pillars ...	Each	3	
n	Chunam moulding 6" x ½" all round ventilators ...	R.ft.	66	
3a	Cuddapah slab flooring 1½" thick on 3" lime concrete and cement pointed including thread lines.	Sqr.	1·94	
b	First class Mangalore tiled flooring on 3" lime concrete and cement pointed.	„	3·70	
4	Roofing with Madras terrace 9" thick including plastering, etc., complete.	„	6·31	
5a	Teakwood work with wood oiling two coats ...	C.ft.	29·71	
b	Teakwood door pannelled 1½" thick shutters with fixtures	S.ft.	56	

Sl. No.	Item	Unit	Quantity	Rate
c	Teakwood windows with glazed shutters $1\frac{1}{4}''$ with iron bars 5/8" dia., with fixtures, etc., complete (shutters to be in four leaves.)	S.ft.	70	Rs.
d	Chocolate painting two coats	Sqr.	2·02	
6	Ventilators of cement concrete honey comb work $1\frac{1}{2}''$ thick slab fixed, complete.	S.ft.	27	
7	Steel work fixed complete with two coats of painting (Dorman Long & Co., make.)	Cwt.	26·4	
8	Fixing wire gauge shutters with teakwood battens. ..	S.ft.	63	
9	Rain water down pipes 3" dia. fixed, complete ...	R.ft.	156	
10	Brick in mortar and chunam plaster, etc., complete preparing brackets as per design.	Each	10	
	Constructing one Bloch of Cooly Quarters.			
1	Earthwork excavation and filling in basement including a lead of 50'.	C.yd.	40	
2a	Lime mortar stone jelly in concrete foundation ...	C.ft.	333	
b	Stone in clay foundation and basement ...	,,	948	
c	Burnt brick in clay superstructure	,,	2,460	
d	6" plain cornice built in burnt brick in mortar and chunam plaster, etc., complete.	R.ft.	72	
e	Stone slabs 4" thick roughly dressed and set in motar ...	S.ft.	159	
f	Stone slabs 4" thick roughly dressed for stone pillars including cutting slots for bressemers.	,,	26	
g	Chunam plastering two coats	,,	53·74	
h	Chunam pointing with thread lines	,,	1·01	
i	White and colour washing two coats	,,	54·75	
j	Constructing sinks with drain pipes complete ...	Each.	4	
k	Stone mortar pestle including fixing, complete ..	,,	4	
3	Flooring with 3" concrete and cement plaster $\frac{1}{4}''$ thick on top.	Sqr.	7·97	
4a	Roofing with 1st class Mangalore tiles on teakwood reepers 2" x 1" including cement pointing and chunam borders, at ends of roof wherever necessary.	,,	11·40	
b	Ridge tiles set in mortar and cement pointed ...	R.ft.	22	
c	Ventilating tiles set in mortar and cement pointed ...	Each	16	
5a	Matty wood wrought and put up with two coats of wood oil.	C.ft.	41·71	
b	Galvanized iron sheet door with teakwood frame, bolts hinges, etc., (frame 4" x $3\frac{1}{2}''$), complete.	S.ft.	78	
c	Galvanized iron sheet windows with teakwood frame with iron bar, etc., complete (frame $3\frac{3}{4}''$ x 3").	,,	70	
d	Teakwood ventilators glazed with wire gauge shutters fixed, complete.	,,	24	
e	Chocolate painting 2 coats	Sqr.	3·2	
6	Galvanized iron sun shades with teak frames with painting.	Each	4	
	Constructing 2 Units of Lat ine.			
1	Earthwork excavation	C.yd.	4	
2a	Stone in clay foundation and basement	C.ft.	130	
b	Burnt brick in motar superstructure	,,	196	
c	Chunam pointing	Sqr.	0·56	
d	Do plastering	,,	4·91	
e	White and colour washing 2 coats	,,	5·47	
f	Cement plastering $\frac{1}{2}'$ thick	,,	0·79	
g	Tar washing 2 coats	,,	0·63	
3	Flooring with 3" concrete and cement plastering $\frac{1}{2}''$ thick.	,,	0·38	
4a	Providing galvanized iron sheet tubs 12" x 6" complete with tarring.	Each	6	
5	Providing outlets and constructing drains and sinks if necessary.	L. S.	1 item	